

# Vera C. Rubin Observatory Data Management

# **Network Verification Elements**

Joshua Hoblitt, Jeff Kantor

LDM-732

Latest Revision: 2023-07-10

Draft Revision NOT YET Approved – This Rubin Observatory document has been approved as a Content-Controlled Document by the Rubin Observatory DM Change Control Board. If this document is changed or superseded, the new document will retain the Handle designation shown above. The control is on the most recent digital document with this Handle in the Rubin Observatory digital archive and not printed versions. Additional information may be found in the corresponding DM RFC. – Draft Revision NOT YET Approved



# Abstract

The Network Verification Elements document and associated LSST Verification and Validation (LVV) Jira project present the flow-down of specifications from higher level documents to the Observatory Network (as defined in LSE-61 Data Management System (DMS) Requirements), as well as defining the methods and resources that will be used to verify that network requirements have been met.



ii



# **Change Record**

Version	Date	Description	Owner name
	2020-02-21	Document ready for CCB approval	J. Kantor
1.0	2020-05-15	Document approved (RFC-674)	J. Kantor
2.0	2022-09-19	Update title, scope, and referenced DMSR re-	J. Hoblitt
		quirements	

Document source location: https://github.com/lsst/ldm-732 Version from source repository: fb60c02



# Contents

1	Intro	oduction	1
	1.1	Scope	1
	1.2	Specification Flow-down	2
	1.3	LSST Verification and Validation (LVV) Jira project	3
	1.4	Verification and Validation Schedule and Resources	3
	1.5	Applicable Documents	3
2	DM	- NETWORK Verification Elements	4
	2.1	[LVV-71] DMS-REQ-0168-V-01: Summit Facility Data Communications	4
	2.2	[LVV-73] DMS-REQ-0171-V-01: Summit to Base Network	6
	2.3	[LVV-74] DMS-REQ-0172-V-01: Summit to Base Network Availability	8
	2.4	[LVV-75] DMS-REQ-0173-V-01: Summit to Base Network Reliability	9
	2.5	[LVV-76] DMS-REQ-0174-V-01: Summit to Base Network Secondary Link	10
	2.6	[LVV-77] DMS-REQ-0175-V-01: Summit to Base Network Ownership and Opera-	
		tion	11
	2.7	[LVV-81] DMS-REQ-0180-V-01: Base to Archive Network	12
	2.8	[LVV-82] DMS-REQ-0181-V-01: Base to Archive Network Availability	13
	2.9	[LVV-83] DMS-REQ-0182-V-01: Base to Archive Network Reliability	14
	2.10	[LVV-84] DMS-REQ-0183-V-01: Base to Archive Network Secondary Link	15
	2.11	[LVV-88] DMS-REQ-0188-V-01: Archive to Data Access Center Network	16
	2.12	[LVV-89] DMS-REQ-0189-V-01: Archive to Data Access Center Network Availabil-	
		ity	17
	2.13	[LVV-90] DMS-REQ-0190-V-01: Archive to Data Access Center Network Reliability	18
	2.14	[LVV-91] DMS-REQ-0191-V-01: Archive to Data Access Center Network Secondary	
		Link	19
	2.15	[LVV-183] DMS-REQ-0352-V-01: Base Wireless LAN (WiFi)	20
	2.16	[LVV-18491] DMS-REQ-0352-V-02: Base Voice Over IP (VOIP)	21

# A Traceability

22



B References	23
C Acronyms	24



# **Network Verification Elements**

# **1** Introduction

# 1.1 Scope




FIGURE 1: A diagram depicting the inter-facility network data transfers identified in LSE-61.

This document pertains only to the verification of the network infrastructure, not the applications and services that use the network, specifically, up to OSI Layer 3 for the Summit facility, the Base Facility, Summit to Base communication, Base to Archive communication, and Archive to the [Chilean] Data Access Center communication. The transfer of data products, such as alert streams or pixel data, from the US Data Facility to parties external to the observatory are explicitly out of scope.

As such, all of the Verification Elements defined in the LSST Verification and Validation (LVV) Jira project and presented in this document are Lower Level (LL) in the System Engineering test hierarchy.

LL corresponds to Data Management Subsystem Integration. Where appropriate, additional comments regarding Same Level (SL) which corresponds to LSST System Integration, and Higher Level (HL) which corresponds to LSST Commissioning, are called out in the Verification Elements.

Note that significant testing of the networks occurs prior to subsystem and system integration, i.e. prior to verification, as discussed in LSST LHN End-to-End Plan and associated documentation in Collection-3758.



# **1.2 Specification Flow-down**

# 1.2.1 Data Management Subsystem Requirements Flow-down

The Data Management Subsystem Requirements (DMSR) (LSE-61) drive the LSST Observatory Network Design. The specific DMSR requirements that directly drive network design are listed here for convenience.

Name	ID
1.3.1 Nightly Data Accessible Within Specified Time	DMS-REQ-0004 (Priority: 1b)
1.6.4 Constraints on Level 1 Special Program Products Generation	DMS-REQ-0344 (Priority: 2)
2.2.3 Transient Alert Distribution	DMS-REQ-0002 (Priority: 1b)
2.2.3.1 Alert Stream Distribution	DMS-REQ-0391 (Priority: 2)
2.2.3.2 Alert Delay and Failure Tolerances	DMS-REQ-0392 (Priority: 2)
2.2.7 DIASource Precovery	DMS-REQ-0287 (Priority: 1b)
2.2.9 Solar System Objects Available Within Specified Time	DMS-REQ-0089 (Priority: 1b)
4.1.2 Engineering & Facility Database Archive	DMS-REQ-0102 (Priority: 1b)
4.4.1 Summit to Base Network	DMS-REQ-0171 (Priority: 1a)
4.4.2 Summit to Base Network Availability	DMS-REQ-0172 (Priority: 1b)
4.4.3 Summit to Base Network Reliability	DMS-REQ-0173 (Priority: 1b)
4.4.4 Summit to Base Network Secondary Link	DMS-REQ-0174 (Priority: 1b)
4.4.5 Summit to Base Network Ownership and Operation	DMS-REQ-0175 (Priority: 1b)
4.5.5 Base Wireless LAN (WiFi)	DMS-REQ-0352 (Priority: 2)
4.6.1 Base to Archive Network	DMS-REQ-0180 (Priority: 1b)
4.6.2 Base to Archive Network Availability	DMS-REQ-0181 (Priority: 1b)
4.6.3 Base to Archive Network Reliability	DMS-REQ-0182 (Priority: 1b)
4.6.4 Base to Archive Network Secondary Link	DMS-REQ-0183 (Priority: 1b)
4.8.1 Archive to Data Access Center Network	DMS-REQ-0188 (Priority: 1b)
4.8.2 Archive to Data Access Center Network Availability	DMS-REQ-0189 (Priority: 1b)
4.8.3 Archive to Data Access Center Network Reliability	DMS-REQ-0190 (Priority: 1b)
4.8.4 Archive to Data Access Center Network Secondary Link	DMS-REQ-0191 (Priority: 1b)

# 1.2.2 Observatory System Specifications Flow-down

Note that the Observatory System Specifications (OSS) (LSE-30) also include general requirements on security, disaster recovery, physical environment (including seismic activity), and shipping which are flowed down to the subsystems, and while they apply to all subsystems, including the networks, they will be tested and verified in the Telescope and Data Management Subsystem Integration Tests and in the LSST Commissioning Phase, as part of the LSST System Integration Test. Those requirements are excluded from this specification and the associated verification matrix, as they will be addressed during system integration testing.

# **1.3 LSST Verification and Validation (LVV) Jira project**

The LSST Verification and Validation (LVV) Jira project lists the specifications within or derived from, and traceable to, the DMSR specifications, in Verification Elements that also specify the methods to be used to verify, the responsible parties, and additional notes regarding verification, per the LSE-160 LSST Verification and Validation Process. The Verification Elements then have one or more Test Cases associated with them that describe the implementation of the verification activities in terms of specific tests to be executed. Those Test Cases are then scheduled via Test Plans and Campaigns, and executed with results reported in Test Cycles.

# **1.4 Verification and Validation Schedule and Resources**

The schedule and resources required for network verification are defined in the LSST Project Management Control System (PMCS). They are covered by the final integration test activities in the WBS elements 02C.08.03 Long-Haul Networks. In each Verification Element, a crossreference to the ID of the appropriate predecessor PMCS activities is provided in the preconditions field.

# **1.5 Applicable Documents**

- LSE-61 LSST DM Subsystem Requirements
- LSE-78 LSST Observatory Network Design
- LSE-160 Verification and Validation Process
- LSE-309 Summit to Base Information Technology and Communication (ITC) Design
- LSE-479 Network Technical Document



# 2 DM - NETWORK Verification Elements

The following is the list of verification elements defined in the context of the NETWORK component<sup>1</sup> of the DM subsystem.

# 2.1 [LVV-71] DMS-REQ-0168-V-01: Summit Facility Data Communications

Jira Link	Assignee	Status	Test Cases
LVV-71	Joshua Hoblitt	Covered	LVV-T1097
		Covereu	LVV-T2338

## Verification Element Description:

Verify that:

- Summit Base Network has been properly implemented in Summit and Base facilities
- Summit Base Network is properly integrated with Summit Control Network and DAQ/-Camera Data Backbone

Verify that OCS/DMCS triggers read-out from DAQ and queries EFD. verify that data from EFD and camera are accepted and transferred to the Summit DWDM. Requirement does not include data transfer to base (LVV-73) or from base to archive center (LVV-81, LVV-82, LVV-83).

Requirement Details				
Requirement ID DMS-REQ-0168				
Requirement Priority	1a			
Requirement Description and Discussion:				

**Specification:** The DMS shall provide data communications infrastructure to accept science data and associated metadata read-outs, and the collection of ancillary and engineering data, for transfer to the base facility.

Upper Level Requirement OSS-REQ-0002 The Summit Facility

<sup>1</sup>Major product in the subsystem.



#### 2.1.1 Test Cases Summary

LVV-T1097	1097 Verify Summit Facility Network Implementation				
Owner	Status	Version	<b>Critical Event</b>	Verification Type	
Jeff Kantor	Draft	1	false	Test	
Objective:					

Verify that data acquired by a AuxTel DAQ can be transferred to Summit DWDM and loaded in the EFD without problems.

LVV-T2338	Replicated telemetry data agrees with telemetry produced at the summit				
Owner	Status	Version	<b>Critical Event</b>	Verification Type	
Simon Krughoff	Defined	1	false	Demonstration	
Objective:					

# Show that telemetry data can be accessed from the replicated EFD. Further, show that the values in the replicated database agree with the values in the summit EFD over a specified time range and set of topics.

This test case provides partial coverage of the requirement DMS-REQ-0168, Summit Facility Data Communications: "The DMS shall provide data communications infrastructure to accept science data and associated metadata readouts, and **the collection of ancillary and engineering data**, for transfer to the base facility.", as adapted to the current design for EFD replication (see DMTN-082).



# 2.2 [LVV-73] DMS-REQ-0171-V-01: Summit to Base Network

Jira Link	Assignee	Status	Test Cases
LVV-73	Joshua Hoblitt	In Varification	LVV-T1168
LVV-75	Joshua Hobiltt		LVV-T1612

# Verification Element Description:

This requirement must be tested in sequence and collect performance metrics (both DAQ and Control sides unless noted):

- 1. ISO OSI Layer 1 Physical (fibers with test data from OTDR, AURA does test)
- 2. ISO OSI Layer 2 Data Link (DWDM equipment, line cards, with test data from multichannel/lightwave/channel analyzer, Installer does test, AURA certify)
- 3. ISO Layer 3 minimal (DWDM with 2 x 10 Gbps ethernet port client cards with test data from 4 windows test boxes, 2 on each side, Installer does test, AURA certify, can repeat as part of #4 with DAQ)
- 4. ISO Layer 3 full (22 x 10 Gbps ethernet ports on DAQ side with test data from DAQ test stand, AURA, Camera DAQ team do test). Transfer data between summit and base over uninterrupted 1 day period. Demonstrate transfer of data at or exceeding rates specified in LDM-142.

	Requirement Details		
Requirement ID	DMS-REQ-0171		
Requirement Priority 1a			
Requirement Description and Discussion:			

**Specification:** The DMS shall provide communications infrastructure between the Summit Facility and the Base Facility sufficient to carry scientific data and associated metadata for each image in no more than time **summTo-BaseMaxTransferTime**.

Requirement Parameters	<pre>summToBaseMaxTransferTime = 2[second] Maximum time interval to transfer a</pre>			
	full Crosstalk Corrected Exposure and all related metadata from the Summit Facility			
to the Base		у.		
Upper Level Requirement	OSS-REQ-0003	The Base Facility		
opper Lever Requirement	OSS-REQ-0127	Level 1 Data Product Availability		



#### 2.2.1 Test Cases Summary

LVV-T1168 Verify Summit - Base Network Integration				
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Approved	1	false	Inspection
Objective:				

Verify the integration of the summit to base network by demonstrating a sustained and uninterrupted transfer of data between summit and base over 1 day period at or exceeding rates specified in LDM-142. Done in 3 phases in collaboration with equipment/installation vendors (see test procedure).

LVV-T1612	Verify Summit - Base Network Integration (System Level)			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Inspection
Objective				

#### **Objective:**

Verify ISO Layer 3 full (22 x 10 Gbps ethernet ports on DAQ side with test data from DAQ test stand, AURA, Camera

DAQ team do test). Demonstrate transfer of data at or exceeding rates specified in LDM-142.



## 2.3 [LVV-74] DMS-REQ-0172-V-01: Summit to Base Network Availability

Jira Link	Assignee	Status	Test Cases
LVV-74	Joshua Hoblitt	Covered	LVV-T185

#### **Verification Element Description:**

This requirement needs the network link to be active for a calculated amount of time (at least 1 week) without failure. Will require extrapolating from test and historical data as failures are rare. Monthly operating statistics will be acquired during commissioning. Demonstrate transfer of data at or exceeding rates specified in LDM-142, verify achieved average and peak throughput and latency.

Requirement Details			
Requirement ID	DMS-REQ-0172		
Requirement Priority	1b		
Requirement Description	and Discussion:		

Requirement Description and Discussion:

**Specification:** The Summit to Base communications shall be highly available, with Mean Time Between Failures (MTBF) > **summToBaseNetMTBF**.

Requirement Parameters	<pre>summToBaseNetMTBF = 90[day] Mean time between failures, measured over a</pre>		
	1-yr period.		
Upper Level Requirement	OSS-REQ-0373	Unscheduled Downtime Subsystem Allocations	
opper Lever Requirement	DMS-REQ-0161	Optimization of Cost, Reliability and Availability in Order	

#### 2.3.1 Test Cases Summary

LVV-T185	Verify implementation of Summit to Base Network Availability			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Inspection
Objective:				

#### Objective:

Verify the availability of Summit to Base Network by demonstrating that the mean time between failures is less than summToBaseNetMTBF (90 days) over 1 year.



## 2.4 [LVV-75] DMS-REQ-0173-V-01: Summit to Base Network Reliability

Jira Link	Assignee	Status	Test Cases
LVV-75	Joshua Hoblitt	Covered	LVV-T186

#### **Verification Element Description:**

Disconnect, reconnect and recover transfer of data between summit and base. After disconnecting fiber at an intermediate location between summit and base, demonstrate reconnection and recovery to transfer of data at or exceeding rates specified in LDM-142 within MTTR specification. Network operator will provide MTTR data on links during commissioning and operations.

	Requir	ement Details
Requirement ID	DMS-REQ-0173	
Requirement Priority	1b	
Requirement Description	and Discussion:	

Specification: The Summit to Base communications shall be highly reliable, with Mean Time to Repair (MTTR) < summToBaseNetMTTR.

Requirement Parameters	summToBaseNetMTTR = 24[hour] Mean time to repair, measured over a 1-yr pe-		
	riod.		
Upper Level Requirement	OSS-REQ-0373	Unscheduled Downtime Subsystem Allocations	
opper Lever Requirement	DMS-REQ-0161	Optimization of Cost, Reliability and Availability in Order	

#### 2.4.1 Test Cases Summary

LVV-T186	Verify implementation of Summit to Base Network Reliability			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Demonstration
Objective:				

#### Objective:

Verify the reliability of the summit to base network by demonstrating reconnection and recovery to transfer of data at or exceeding rates specified in LDM-142 following a cut in network connection, within MTTR specification. The network operator will provide MTTR data on links during commissioning and operations.



## 2.5 [LVV-76] DMS-REQ-0174-V-01: Summit to Base Network Secondary Link

Jira Link	Assignee	Status	Test Cases
LVV-76	Joshua Hoblitt	Covered	LVV-T187

#### **Verification Element Description:**

This requirement is verified by demonstrating use of a secondary transfer method (redundant fiber network, microwave link, or transportable medium) between Summit and Base capable of transferring 1 night of raw data (nCalibExpDay + nRawExpNightMax = 450 + 2800 = 3250 exposures) within summToBaseNet2TransMax (72 hours).

	Requirem	ent Details
Requirement ID	DMS-REQ-0174	
Requirement Priority	1b	
Requirement Description	and Discussion:	

**Specification:** The Summit to Base communications shall provide at least one secondary link or transport mechanism for minimal operations support in the event of extended outage. This link may include redundant fiber optics, microwaves, or transportable media. It shall be capable of transferring one night's worth of raw data in **summToBaseNet2TransMax** or less.

Requirement Parameters	<pre>summToBaseNet2TransMax = 72[hour] Maximum time to transfer one night of</pre>		
	data via the network secondary link.		
	DMS-REQ-0173	Summit to Base Network Reliability	
Upper Level Requirement	OSS-REQ-0049	Degraded Operational States	
	DMS-REQ-0172	Summit to Base Network Availability	

#### 2.5.1 Test Cases Summary

LVV-T187	Verify implementation of Summit to Base Network Secondary Link			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective				

#### **Objective:**

Verify automated fail-over from primary to secondary equipment in Rubin Observatory DWDM on simulated failure of primary. Verify bandwidth sufficiency on secondary. Verify automated recovery to primary equipment on simulated restoration of primary. Repeat for failure of Rubin Observatory fiber and fail-over to AURA fiber and DWDM. Demonstrate use of secondary in "catch-up" mode.



# 2.6 [LVV-77] DMS-REQ-0175-V-01: Summit to Base Network Ownership and Operation

Jira Link	Assignee	Status	Test Cases
LVV-77	Joshua Hoblitt	Covered	LVV-T188

# **Verification Element Description:**

This requirement is verified by inspecting construction and operations contracts and Indefeasible Rights to Use (IRUs).

	Requirement Details	
Requirement ID	DMS-REQ-0175	
Requirement Priority	1b	
Requirement Description	and Discussion:	

**Specification:** The Summit to Base communications link shall be owned and operated by LSST and/or the operations entity to ensure responsiveness of support.

	DMS-REQ-0173	Summit to Base Network Reliability
Upper Level Requirement	OSS-REQ-0036	Local Autonomous Administration of System Sites
	DMS-REQ-0172	Summit to Base Network Availability

## 2.6.1 Test Cases Summary

LVV-T188	Verify implementation of Summit to Base Network Ownership and Operation			rk Ownership and
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Inspection
Objective:				

Verify Summit to Base Network Ownership and Operation by LSST and/or the operations entity by inspection of construction and operations contracts and Indefeasible Rights.



#### 2.7 [LVV-81] DMS-REQ-0180-V-01: Base to Archive Network

Jira Link	Assignee	Status	Test Cases
LVV-81	Joshua Hoblitt	Covered	LVV-T193

#### **Verification Element Description:**

This requirement is verified by transferring simulated or pre-cursor image data and metadata between base and archive over an uninterrupted 1 day period. Analyze the network performance and show that data can be transferred by DAQ within the required time.

	Requirement Details
Requirement ID	DMS-REQ-0180
Requirement Priority	1b
Requirement Description	and Discussion:

**Specification:** The DMS shall provide communications infrastructure between the Base Facility and the Archive Center sufficient to carry scientific data and associated metadata for each image in no more than time **base-ToArchiveMaxTransferTime**.

Requirement Parameters	<pre>baseToArchiveMaxTransferTime = 5[second] Maximum time interval to transfer</pre>		
	a full Crosstalk Corrected Exposure and all related metadata from the Base Facility		
	to the Archive Center.		
	OSS-REQ-0053	Base-Archive Connectivity Loss	
Upper Level Requirement	OSS-REQ-0055	Base Updating from Archive	
	DMS-REQ-0162	Pipeline Throughput	

#### 2.7.1 Test Cases Summary

LVV-T193	Verify implementation of Base to Archive Network			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
hiective:				

#### **Objective:**

Verify that the data acquired by a DAQ can be transferred within the required time, i.e. verify that link is capable of transferring image for prompt processing in oArchiveMaxTransferTime = 5[second], i.e. at or exceeding rates specified in LDM-142.



## 2.8 [LVV-82] DMS-REQ-0181-V-01: Base to Archive Network Availability

Jira Link	Assignee	Status	Test Cases
LVV-82	Joshua Hoblitt	Covered	LVV-T194

#### **Verification Element Description:**

This requirement is verified by transferring data between base and archive over uninterrupted 1 week period, modeling to extrapolate to an annual failure rate, and verifying that is within the requirement.

	Requirement Details	
Requirement ID	DMS-REQ-0181	
Requirement Priority	1b	
Requirement Description	and Discussion:	

**Specification:** The Base to Archive communications shall be highly available, with MTBF > **baseToArchNetMTBF**.

Requirement Parameters	baseToArchNetMTBF = 180[day] Mean time between failures, measured over a		
	1-yr period.		
	OSS-REQ-0053	Base-Archive Connectivity Loss	
Upper Level Requirement	DMS-REQ-0162	Pipeline Throughput	
	DMS-REQ-0161	Optimization of Cost, Reliability and Availability in Order	

#### 2.8.1 Test Cases Summary

LVV-T194	Verify implementation of Base to Archive Network Availability			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective:				

Verify the availability of the Base to Archive Network communications by demonstrating that it meets or exceeds a mean time between failures, measured over a 1-yr period of MTBF > baseToArchNetMTBF (180[day])



## 2.9 [LVV-83] DMS-REQ-0182-V-01: Base to Archive Network Reliability

Jira Link	Assignee	Status	Test Cases
LVV-83	Joshua Hoblitt	Covered	LVV-T195

#### **Verification Element Description:**

Disconnect, reconnect and recover transfer of data between summit and base, after disconnecting fiber at an intermediate location between base and archive

	Requireme	nt Details
Requirement ID	DMS-REQ-0182	
Requirement Priority	1b	
Requirement Description and Discussion:		

**Specification:** The Base to Archive communications shall be highly reliable, with MTTR < **baseToArchNetMTTR**.

Requirement Parameters	baseToArchNetMTTR = 48[hour] Mean time to repair, measured over a 1-yr pe-		
	riod.		
Upper Level Requirement	OSS-REQ-0053	Base-Archive Connectivity Loss	
opper Lever Requirement	DMS-REQ-0161	Optimization of Cost, Reliability and Availability in Order	

#### 2.9.1 Test Cases Summary

LVV-T195	Verify implementation of Base to Archive Network Reliability			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective:				

Verify Base to Archive Network Reliability by demonstrating that the network can recover from outages within baseToArchNetMTTR = 48[hour].



## 2.10 [LVV-84] DMS-REQ-0183-V-01: Base to Archive Network Secondary Link

Jira Link	Assignee	Status	Test Cases
LVV-84	Joshua Hoblitt	Covered	LVV-T196

#### **Verification Element Description:**

This requirement is verified by disconnecting the primary link, failing over to the secondary link, reconnecting primary link, and failing back to primary link, while verifying data is transferred within required times.

	Requirement Details	
Requirement ID	DMS-REQ-0183	
Requirement Priority	1b	
Requirement Description	and Discussion:	

**Specification:** The Base to Archive communications shall provide a secondary link or transport mechanism (e.g. protected circuit) for operations support and "catch up" in the event of extended outage which is capable of transferring data at least the same rate as the required minimum capacity of the primary link.

	DMS-REQ-0181	Base to Archive Network Availability
Upper Level Requirement	DMS-REQ-0182	Base to Archive Network Reliability
	OSS-REQ-0049	Degraded Operational States

#### 2.10.1 Test Cases Summary

LVV-T196	Verify implementation of Base to Archive Network Secondary Link			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective:				

Verify Base to Archive Network Secondary Link failover and capacity, and subsequent recovery primary. Demonstrate the use of the secondary path in "catch-up" mode.



## 2.11 [LVV-88] DMS-REQ-0188-V-01: Archive to Data Access Center Network

Jira Link	Assignee	Status	Test Cases
LVV-88	Joshua Hoblitt	Covered	LVV-T200

#### **Verification Element Description:**

This requirement is verified by transferring data between archive and both DACs over uninterrupted 1 day period, analyzing the network performance, and verifying that data can be transferred within the required time.

	Requirement Details	
Requirement ID	DMS-REQ-0188	
Requirement Priority	1b	
Requirement Description	and Discussion:	

**Specification:** The DMS shall provide communications infrastructure between the Archive Center and Data Access Centers sufficient to carry scientific data and associated metadata in support of community and EPO access. Aggregate bandwidth for data transfers from the Archive Center to Data Centers shall be at least **archToDacBandwidth**.

Requirement Parameters	archToDacBandwidth = 10000[megabit per second] Aggregate bandwidth ca-	
	pacity for data transfers between the Archive and Data Access Centers.	
Upper Level Requirement		

## 2.11.1 Test Cases Summary

LVV-T200	Verify implementation of Archive to Data Access Center Network			
Owner	Status Version Critical Event Verification 1			
Jeff Kantor	Draft	1	false	Test
Objective:				

Verify archiving of data to Data Access Center Network at or exceeding rates specified in LDM-142, i.e at archTo-DacBandwidth = 10000[megabit per second].



# 2.12 [LVV-89] DMS-REQ-0189-V-01: Archive to Data Access Center Network Availability

Jira Link	Assignee	Status	Test Cases
LVV-89	Joshua Hoblitt	Covered	LVV-T201

# **Verification Element Description:**

This requirement needs the network link to be active for a calculated amount of time (at least 1 week) without failure. This will require modeling as failures are rare, so an annual MTBF will be estimated from test results.

	Requirem	ent Details	
Requirement ID	DMS-REQ-0189		
Requirement Priority 1b			
Requirement Description	and Discussion:		

**Specification:** The Archive to Data Access Center communications shall be highly available, with MTBF > **archTo-DacNetMTBF**.

Requirement Parameters	archToDacNetMTBF = 180[day] Mean Time Between Failures for data service be-		
	tween Archive and DACs, averaged over a one-year period.		
Upper Level Requirement	DMS-REQ-0161	Optimization of Cost, Reliability and Availability in Order	

# 2.12.1 Test Cases Summary

LVV-T201	Verify implementation of Archive to Data Access Center Network Availability			s Center Network
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective:				

Verify availability of archiving to Data Access Center Network using test and historical data of or exceeding arch-ToDacNetMTBF= 180[day].



# 2.13 [LVV-90] DMS-REQ-0190-V-01: Archive to Data Access Center Network Reliability

Jira Link	Assignee	Status	Test Cases
LVV-90	Joshua Hoblitt	Covered	LVV-T202

# **Verification Element Description:**

This requirement is verified by reconnecting and recovering transfer of data between archive and DACs, after disconnecting fiber at an intermediate location between archive and DACs.

	Requirement Details		
Requirement ID	DMS-REQ-0190		
Requirement Priority 1b			
Requirement Description and Discussion:			

**Specification:** The Archive to Data Access Center communications shall be highly reliable, with MTTR < **archTo-DacNetMTTR**.

<b>Requirement Parameters</b>	archToDacNetMTTR = 48[hour] Mean time to repair, measured over a 1-yr period.		
Upper Level Requirement	DMS-REQ-0161	Optimization of Cost, Reliability and Availability in Order	

# 2.13.1 Test Cases Summary

LVV-T202	Verify implementation of Archive to Data Access Center Network Re- liability			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective				

#### **Objective:**

Verify the reliability of Archive to Data Access Center Network by demonstrating successful failover and capacity to the secondary part and subsequent recovery to primary within or exceeding chToDacNetMTTR = 48[hour].



# 2.14 [LVV-91] DMS-REQ-0191-V-01: Archive to Data Access Center Network Secondary Link

Jira Link	Assignee	Status	Test Cases
LVV-91	Joshua Hoblitt	Covered	LVV-T203

# Verification Element Description:

This requirement is verified by reconnecting and recovering transfer of data between archive and DACs, after disconnecting fiber at an intermediate location between archive and DACs.

	Requirement Details
Requirement ID	DMS-REQ-0191
Requirement Priority	1b
Requirement Description	and Discussion:

**Specification:** The Archive to Data Access Center communications shall provide secondary link or transport mechanism (e.g. protected circuit) for operations support and "catch up" in the event of extended outage.

Upper Level Requirement	DMS-REQ-0189	Archive to Data Access Center Network Availability
opper Lever Requirement	DMS-REQ-0190	Archive to Data Access Center Network Reliability

# 2.14.1 Test Cases Summary

LVV-T203	Verify implementation of Archive to Data Access Center Network Secondary Link			
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Kian-Tat Lim	Draft	1	false	Test
hiastiva				

#### **Objective:**

Verify the Archive to Data Access Center Network via Secondary Link by simulating a failure on the primary path and capacity on the secondary path.



## 2.15 [LVV-183] DMS-REQ-0352-V-01: Base Wireless LAN (WiFi)

Jira Link	Assignee	Status	Test Cases
LVV-183	Joshua Hoblitt	Covered	LVV-T192

#### Verification Element Description:

At Base Facility, connect to WiFi, test connection speed, i.e. send email, browse web, and retrieve files from the Internet.

	Requirement Details
Requirement ID	DMS-REQ-0352
Requirement Priority	2
Requirement Description	and Discussion:

**Specification:** The Base LAN shall provide **minBaseWiFi** Wireless LAN (WiFi) and Wireless Access Points in the Base Facility to support connectivity of individual user's computers to the network backbones.

Requirement Parameters	minBaseWifi = 1000[megabit per second] Maximum allowable	e outage of active
	DM production.	
Upper Level Requirement	OSS-REQ-0003 The Base Facility	

# 2.15.1 Test Cases Summary

LVV-T192	Verify implementation of Base Wireless LAN (WiFi)			i)
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective:				

Objective:

Verify as-built wireless network at the Base Facility supports minBaseWiFi bandwidth (1000 Mbs).



## 2.16 [LVV-18491] DMS-REQ-0352-V-02: Base Voice Over IP (VOIP)

Jira Link	Assignee	Status	Test Cases
LVV-18491	Joshua Hoblitt	Covered	LVV-T181

#### **Verification Element Description:**

Verify (a) planned and (b) as-built VOIP at the Base Facility is operational and performs as expected (i.e. sufficient number of extensions allocated properly, no frequent drop-outs, no frequent jaggies on video, etc.). Test voice calls and videoconferening.

	Requirement Details
Requirement ID	DMS-REQ-0352
Requirement Priority	2
Requirement Description	and Discussion:

**Specification:** The Base LAN shall provide **minBaseWiFi** Wireless LAN (WiFi) and Wireless Access Points in the Base Facility to support connectivity of individual user's computers to the network backbones.

Requirement Parameters	minBaseWifi = 1000[megabit per second] Maximum allowable outage of active
	DM production.
Upper Level Requirement	OSS-REQ-0003 The Base Facility

## 2.16.1 Test Cases Summary

LVV-T181	Verify Base	Voice Over IP (VC	DIP)	
Owner	Status	Version	<b>Critical Event</b>	Verification Type
Jeff Kantor	Draft	1	false	Test
Objective:				

Verify as-built VOIP at the Base Facility is operational and performs as expected (i.e. sufficient number of extensions allocated properly, no frequent drop-outs, no frequent jaggies on video, etc.) on both voice calls and videoconferening.



# **A** Traceability

Requirements	Verification Elements	Test Cases
DMS-REQ-0168	LVV-71	LVV-T1097
		LVV-T2338
DMS-REQ-0171	LVV-73	LVV-T1168
		LVV-T1612
DMS-REQ-0172	LVV-74	LVV-T185
DMS-REQ-0173	LVV-75	LVV-T186
DMS-REQ-0174	LVV-76	LVV-T187
DMS-REQ-0175	LVV-77	LVV-T188
DMS-REQ-0180	LVV-81	LVV-T193
DMS-REQ-0181	LVV-82	LVV-T194
DMS-REQ-0182	LVV-83	LVV-T195
DMS-REQ-0183	LVV-84	LVV-T196
DMS-REQ-0188	LVV-88	LVV-T200
DMS-REQ-0189	LVV-89	LVV-T201
DMS-REQ-0190	LVV-90	LVV-T202
DMS-REQ-0191	LVV-91	LVV-T203
DMS-REQ-0352	LVV-183	LVV-T192
	LVV-18491	LVV-T181

Note that some of the requirements listed in this traceability table may be related with additional Verification Elements not in the scope of *DM* component *NETWORK* subcomponent Verification, and therefore not listed here.

# **B** References

- [1] **[LSE-30]**, Claver, C.F., The LSST Systems Engineering Integrated Project Team, 2018, Observatory System Specifications (OSS), LSE-30, URL https://ls.st/LSE-30
- [2] [LSE-61], Dubois-Felsmann, G., Jenness, T., 2019, <u>Data Management System (DMS) Requirements</u>, LSE-61, URL https://lse-61.lsst.io/, Vera C. Rubin Observatory
- [3] [LDM-142], Kantor, J., 2017, Network Sizing Model, LDM-142, URL https://ls.st/LDM-142
- [4] [LSE-309], Kantor, J., 2017, Summit to Base Information Technology and Communication (ITC) Design, LSE-309, URL https://ls.st/LSE-309
- [5] **[LSE-78]**, Lambert, R., Kantor, J., Huffer, M., et al., 2017, LSST Observatory Network Design, LSE-78, URL https://ls.st/LSE-78
- [6] **[LSE-479]**, Network Engineering Team (NET), 2020, <u>Network Technical Document</u>, LSE-479, URL https://ls.st/LSE-479
- [7] [LSE-160], Selvy, B., 2013, Verification and Validation Process, LSE-160, URL https://ls. st/LSE-160



# C Acronyms

Acronym	Description		
CCB	Change Control Board		
DAQ	Data Acquisition System		
DM	Data Management		
DMCS	Data Management Control System		
DMS	Data Management Subsystem		
DMS-REQ	Data Management top level requirements (LSE-61)		
DMSR	DM System Requirements; LSE-61		
DMTN	DM Technical Note		
DWDM	Dense Wave Division Multiplex		
EFD	Engineering and Facility Database		
EPO	Education and Public Outreach		
HL	Higher Level		
IP	Internet Protocol		
ISO	International Standards Organization		
ITC	Information Technology Center		
LAN	Local Area Network		
LDM	LSST Data Management (Document Handle)		
LHN	Long-Haul Networks		
LL	Lower Level		
LSE	LSST Systems Engineering (Document Handle)		
LSST	Legacy Survey of Space and Time (formerly Large Synoptic Survey Tele- scope)		
LVV	LSST Verification and Validation (Jira project)		
MTBF	Mean Time Between Failures		
MTTR	Mean Time to Repair		
OCS	Observatory Control System		
OSI	Open System Interconnect		
OSS	Observatory System Specifications; LSE-30		
OTDR	Optical Time Domain Reflectometer		
PMCS	Project Management Controls System		
RFC	Request For Comment		
SL	Same Level		

DRAFT NOT YET APPROVED – The contents of this document are subject to configuration control by the Rubin Observatory DM Change Control Board. – DRAFT NOT YET APPROVED



US	United States
VOIP	Voice Over Internet Protocol
WBS	Work Breakdown Structure